



- KEY.**
- Existing Bridge structure proposed for alteration. Proposed alterations to be agreed with Environment Agency. Footway widened by 2.0m
 - Proposed carriageway construction with 'Tegular Cobble' finish
 - Proposed footway construction with 'Tegular' block finish
 - Proposed carriageway / footway construction with 'Macadam' finish. Red chippings to be used in carriageway.
 - Proposed footway construction with paved finish.
 - Proposed carriageway construction with block paved finish.
 - Proposed carriageway construction with Hot rolled asphalt finish
 - Proposed Red 'Blister' tactile paving
 - Proposed buff 'Blister' tactile paving
 - Proposed kerb line
 - Proposed concrete edge restraint
 - Proposed concrete channel
 - Proposed 'Darlington' style bollard with retroreflective paneling
 - Proposed 'Specimen' Treeshrub planting within hard landscaping. Appropriate grids, irrigation, tree pit or planter and planting details to be agreed once after consultation with utility companies
 - Primary traffic signal head
 - Secondary traffic signal head
 - Short pole with push button
 - Belisha Beacon pole with supplementary lighting
 - Sign post

Notes

Existing parking restrictions (double yellow lines) are shown in orange.

All road markings to be in accordance with the 'Traffic Signs Regulations and General Directions 2016'

<p>1. No. space lost in Victoria Rd North back. Speed limit signs changed to 20 zone signs. 20 zone extended on Park lane and cliffon rd as far back as Waverley terrace</p>	<p>18/12/19 DL</p>
--	--------------------

Rev/Amst.	Amendment	Date	Approved
-----------	-----------	------	----------

DARLINGTON BOROUGH COUNCIL

17 Allington Way
Darlington
DL1 4QB

Tel : (01325) 405000
Fax: (01325) 388724

Project No. TP818	Project Title Rethinking Victoria Rd
----------------------	---

Drawn By DL	Date 02/12/19	Drawing No. 001	Scale 1:500@A0
Approved By NW	Date 03/12/19	Rev/Amst. 0/A	